



सुनकोशी गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय



च.नं. १८८९
प.सं. ०८२/०८३



बागमती प्रदेश, नेपाल
मिति: २०८२/१२/१९

जो जससँग सम्बन्धित छ।

विषय :- दररेट पेश गर्ने सम्बन्धमा ।

प्रस्तुत विषयमा सुनकोशी गाउँपालिका योजना शाखाको आ.व. २०८२/०८३ को स्वीकृत वार्षिक कार्यक्रम अन्तर्गत पन्चकन्या बर्थिंग सेन्टर सुद्रीढीकरण सुनकोशी-०२ को लागि रु. १०,००,००० र पुरानो झागाझोली स्वास्थ्य चौकी सुदुढीकरण सुनकोशी-०५ को लागि रु. १०,००,००० बजेट विनियोजन भएको हुँदा सूचना प्रकाशन भएको मितिले ७ दिन भित्र (अन्तिम दिन विदा पर्ने भएमा सोको भोलि) सम्म घटाघटमा दररेट पेश गर्न जानकारी गराईन्छ। साथै आशय पत्र पेश गर्दा तपशिल बमोजिमका कागजात पेश गर्न समेत जानकारी गराईन्छ।

१. निर्माण व्यवसायी दर्ता प्रमाणपत्र
२. निर्माण व्यवसायीको इजाजत प्रमाणपत्र
३. स्थायी लेखा नम्बर
४. आ.व. २०८१/२०८२को कर चुक्ता
५. माँग भएको आशय
६. प्रचलित कानून बमोजिमका अन्य कागजातहरू ।

शिवराज पौडेल
प्रमुख प्रशासकीय अधिकृत
शिवराज पौडेल
प्रमुख प्रशासकीय अधिकृत

सुनकोशी गाउँपालिका
गाउँकार्यापालिकाको कार्यालय
रामटार, सिन्धुली, बागमती प्रदेश, नेपाल
कार्यालय कोड नं.: ८०१०३२५०८
निर्माण कार्यको लागत अनुमान रकम

म.ले.प.फारम नं: ५०२
साबिकको फारम नं: NA



म वा परियोजनाको नाम: पन्चकन्या बर्थिंग सेन्टर सुद्रीढीकरण सुनकोशी-०२
योजनाको नाम र कार्यान्वयन हुने स्थल: सु.गा.पा, २ सिन्धुली


आर्थिक वर्ष: 2082/083
बजेट उप शीर्षक न:

क्र.सं.	काम/सेवाको विवरण	इकाई	परिमाण	दर	जम्मा लागत	अनुमानित दरको स्रोत
१	२	३	५	४	६=४*५	७
1	12.5 mm thick cement sand (1:6) plaster Cement sand plaster except ceiling	sqm	102.46			
2	12.5 mm thick cement sand (1:6) plaster Cement sand plaster except ceiling	sqm	549.64			
3	Two coat Distemper paint with primer	sqm	573.61			
4	Porcelain Glazed Tile on 1:4 Cement sand mortar	sqm	32.40			
5	38mm thick flush shutter including sal wood frame with 4 mm thick teak plywood on both side of shutter	sqm	16.25			
6	Fixing 4mm thick glass in wooden frame with wood listy	sqm	16.34			
7	10*10 mm solid core square rod grill on 4.5*20mm iron plate including panting with red oxide and aluminium paint.	sqm	17.89			
8	38mm thick flush shutter including sal wood frame with 26 gauge GI plain sheet on one side of shutter	sqm	6.83			
9	Providing & fixing 1" dia CPVC pipe of flowguard or equivalent including necessary fitting.	Rm	45.00			
10	Providing & fixing 3" dia. PVC pipe 6kg/cm2 all complete including fittings.	Rm	20.00			
11	Providing & fixing 4" dia. PVC pipe all complete including fittings.	Rm	35.00			
12	580 mm Porcelain clay white glazed indian Pan (Hindustan, Parryware, Classica, cera or equivalent)	No	5.00			
13	Providing and fixing in position hand wash basin of size 550x400 mm with pedestal of Hindware or equivalent brand including 1/4" dia cp waste coupling with chain and rubber plug, 1 1/4" dia cp bottle trap, 1 no. of 1/2" dia cp Basin pillar cock, connection to waste line and water lines all complete ready for operation.	No	4.00			
14	Providing & fixing CP long body Bib cock of Jaquar or equivalent brand all complete ready for operation.	No	5.00			
15	Providing & fixing CP Soap dish	No	4.00			
16	Providing & fixing looking mirror (18"x24")	No	4.00			
17	Providing and fixing 7.5cm dia shower rose fancy type with 30cm c p rod	No	2.00			
18	Providing and fixing C P Towel rod	No	3.00			
19	Providing and fixing CP Guard rail with glass	No	3.00			
20	Supply and installation of multi floor trap including stainless steel anti cockroach trap on the floor as mentioned in the drawings	No	5.00			
21	Supply and fitting of PVC water tank with inlet, outlet, overflow, cleanout hole etc.	ltr	1000.00			

शिवराम पौडेल

प्रमुख प्रशासकीय अधिकृत

	Iron tank stand as specified by the site incharge.	No	1.00			
23	Supply of materials and wiring with copper conductor for Light point with 2x1.5 sq. mm. (or 2x3/20) copper cable including circular junction boxes (average length=5.0m)	Point	45.00			
24	Supply of materials and wiring with copper conductor for Power point with 2x2.5 sq. mm. (or 2x7/22) copper cable including HPDE conduit/listi, and junction boxes (average length=5.0m)	Point	30.00			
25	Supply of Concealed type 6" dia. LED light fixture with 10 watt bulb, fixing, testing and comissioning all complete job.	No	30.00			
26	Supply of 5 pin 15 amp. switch socket, fixing, interconnection ,testing and comissioning all complete.	No	17.00			
27	Supply, fixing, testing and commissioning of 1 gang one way switch with plate complete set..	No	6.00			
28	Supply, fixing, testing and commissioning of 4 gang one way switch with plate set complete.	No	10.00			
29	Providing ,fixing inter connection, testing and comissioning of 6-32A DP MCB of IS standard all complete .	No	8.00			
30	Supply and fixing of 6 Way SPN DB Double Cover	no	2.00			
				Sub Total		
				13% Vat		
				2 % contingencies		
				Total		


 शिवराज पौडेल
 प्रमुख प्रशासकीय अधिकृत