



सुनकोशी गाउँपालिका  
गाउँ कार्यपालिकाको कार्यालय



च.नं. १८८९  
प.सं. ०८२/०८३



बागमती प्रदेश, नेपाल  
मिति: २०८२/१२/१९

जो जससँग सम्बन्धित छ।

विषय :- दररेट पेश गर्ने सम्बन्धमा ।

प्रस्तुत विषयमा सुनकोशी गाउँपालिका योजना शाखाको आ.व. २०८२/०८३ को स्वीकृत वार्षिक कार्यक्रम अन्तर्गत पन्चकन्या बर्थिंग सेन्टर सुद्रीढीकरण सुनकोशी-०२ को लागि रु. १०,००,००० र पुरानो झागाझोली स्वास्थ्य चौकी सुदुढीकरण सुनकोशी-०५ को लागि रु. १०,००,००० बजेट विनियोजन भएको हुँदा सूचना प्रकाशन भएको मितिले ७ दिन भित्र (अन्तिम दिन विदा पर्ने भएमा सोको भोलि) सम्म घटाघटमा दररेट पेश गर्न जानकारी गराईन्छ। साथै आशय पत्र पेश गर्दा तपशिल बमोजिमका कागजात पेश गर्न समेत जानकारी गराईन्छ।

१. निर्माण व्यवसायी दर्ता प्रमाणपत्र
२. निर्माण व्यवसायीको इजाजत प्रमाणपत्र
३. स्थायी लेखा नम्बर
४. आ.व. २०८१/२०८२को कर चुक्ता
५. माँग भएको आशय
६. प्रचलित कानून बमोजिमका अन्य कागजातहरू ।

.....  
शिवराज पौडेल  
प्रमुख प्रशासकीय अधिकृत  
शिवराज पौडेल  
प्रमुख प्रशासकीय अधिकृत



स्थानीय सरकार  
सुनकोशी गाउँपालिका  
गाउँ कार्यपालिकाको कार्यालय  
रामटार, सिन्धुली  
बागमती प्रदेश, नेपाल  
कार्यालय कोड नं.: ८०१०३२५०८



सं.सं.प.कार्यक्रम नं. ५०१


निर्माण कार्यको लागत अनुमान

कार्यक्रम / योजनाको नाम: पुरानो झागाझोली स्वास्थ्य चौकी सुदुर्दिकरण सुनकोशी ०५  
कार्यान्वयन हुने स्थल: सु.गा.पा ५ सिन्धुली



वित्तीय वर्ष: २०८२-०८३  
बजेट १०००००

क्र.सं.	काम/सेवाको विवरण	इकाई	परिमाण	दर	जम्मा लागत	अनुमानित दरको स्रोत
	आइटम					
१	२	३	४	५	६ = ४x५	७
A	General Works					
1	Insurance for works materials, contractor's equipment, labour, Employer's staff including third party & insurance against lost or damage to other properties	Ls	1.00	7000.00	7000.00	
2	Information Board	Ls	1.00	1000.00	1000.00	
B	Civil Works					
1	Roadway Excavation in all types of Soil by Mechanical Means . Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer.	Cum	26.47			
2	Broken Stone solling and levelling in foundation including providing stone and transportation upto 30 m	Cum	3.10			
3	1:2:4 P.C.C. work in foundation, wall and floor including material collection & transportation upto 30m ( for 1 cu.m/ 35.28 cft )	Cum	1.27			
4	1:1½: 3 P.C.C. work in super structure, deck, beam, slab including material collection & transportation upto 30m ( for 1 cu.m/ 35.28 cft )	Cu*1	1.47			
5	Curtilment, bent up, binding of MS bars according to the drawing for RCC and its transportation upto 30 m	Kg	108.96			
6	Form works for slab using 19 mm thick water proof plywood and iron prop	Sqm	12.91			
7	5m height hard block stone rubble masonry works in 1:6 cement mortar including transportation upto 10m	Cum	20.52			

  
शिवराज पौडेल  
प्रमुख प्रशासकीय अधिकृत



8	Fabricating and painting different size of iron angle 16 gauge	Kg	172.27		
9	Fabricating and installing 2*2" mesh size 10 S.W.G.G.I Chain Link	Sqm	152.40		
10	Ceramics floor tile in 1:4 cement sand mortar	Sqm	32.23		
11	Ceramics wall tile on wall in 1:4 cement sand mortar	Sqm	47.81		
12	Providing & fixing 4" dia. PVC pipe all complete including fittings.	Rin	21.00		
13	Light point with 2x1.5 sq. mm. (or 2x3/20) copper cable including HPDE conduit/listi, circular and junction boxes (average length=5.0m)	No	11.00		
14	Power point with 2x2.5 sq. mm. (or 2x7/22) copper cable including HPDE conduit/listi, circular and junction boxes (average length=5.0m)	No	6.00		
15	Supply of Concealed type 6" dia. LED light fixture with 10 watt bulb, fixing, testing and commissioning all complete job.	No	11.00		
16	Supply of 5 pin 15 amp. switch socket, fixing, interconnection, testing and commissioning all complete.	No	4.00		
17	Supply, fixing, testing and commissioning of 6 gang one way switch with plate set complete.	No	2.00		
18	Providing, fixing inter connection, testing and commissioning of 6-32A DP MCB of IS standard all complete.	No	2.00		
19	Supply and fixing of 4 Way SPN DB Double Cover	No	1.00		
			<b>Total Amount</b>		
			<b>13 % VAT</b>		
			<b>Sub Total with VAT</b>		
			<b>3% Contingency</b>		
			<b>Provisional Sum</b>		
			<b>Grand Total</b>		